



CITY OF PANAMA CITY BEACH
August 15, 2023

ADDENDUM NO. 3

**PCB23-44 ITB
POLE BARN ENCLOSURE**

Revision:

Addendum No. 2 addressed clarification on the exterior walls requiring 1/2" plywood. Upon further review the City has interrupted the original question posed to imply the following:
Will the exterior walls be required to have 1/2" APA rated wall sheathing?

The installation of house wrap/moisture barrier will be required between the metal wall sheathing and the studs (wall framing).

Question from Addendum 2:

- Clarification on addendum 1, addendum #1 states no house wrap required, will the exterior walls be required to have 1/2 plywood installed before siding is installed or does metal siding attach directly to wood studs, because if plywood is used on walls before installation of siding it seems a moisture barrier would be needed.
Wall section does not show plywood on wall but table says 1/2" plywood.?

Revised Answer:

A. An APA rated 1/2' wall sheathing is to be attached to the wood studs. A wrap/moisture barrier will then be attached to the 1/2" APA rated wall sheathing and then the vertical metal will be attached. Reference S4.00 in the plans.

TYPE PER PLAN	"APA RATED" 1/2" WALL SHEATHING STRUCT 1	10d EDGE NAIL SPACING	WALL STUDS & BLOCKING AT ABUTTING PANEL EDGES	P.T. 3x SILL PLATE TO CONCRETE	2x SOLE PLATE TO RIMBLOCKING	SOLID SAWN OR LSL RIMBLOCKING JOIST MIN. WIDTH	DBL. 2x TOP PLATE CONNECTION TO RIMBLOCKING		5/8" THREADED RODS STEEL BEAM TO SOLE PLATE/TOP PLATE	ALLOWABLE SHEAR (PLF)
				5/8" ANCHOR BOLTS	SDS 1/2" WOOD SCREWS U.O.N.		"LTP" OR "AS5" CLIPS U.O.N.	SDS 1/2" WOOD SCREWS		
6	ONE SIDE	8"o.c.	2x	48"o.c.	16d NAILS @8"o.c.	1/2"	16"o.c.	8"o.c.	16"o.c.	340